

FORM FOR RECEIPT OF ADDENDUM NO 1

NB This form for the receipt of Addendum No 1 must be completed by the Tenderer and emailed **immediately and separately to**

BVi Consulting Engineers
Office 4
126B Suid Street
POLOKWANE

For attention: Mr A. Manamela, Tel. 015 294 5400
Email: am@bvi.co.za

CITY OF POLOKWANE

PM56/2020: COMPLETION OF CURRENT CONSTRUCTION PHASE OF AN RDP COMBO SPORTS COMPLEX AT MOLEPO (MULTI-YEAR)

I/We acknowledge receipt of Addendum No 1 and have noted its contents.

SIGNED ON BEHALF OF TENDERER :

NAME OF SIGNATORY :

NAME AND ADDRESS OF TENDERER :

.....

.....

.....

TEL NO :

EMAIL :

DATE :



CITY OF POLOKWANE

PM56/2020: COMPLETION OF CURRENT CONSTRUCTION PHASE OF AN RDP COMBO SPORTS COMPLEX AT MOLEPO (MULTI-YEAR)

ADDENDUM NO 1

December 2020

ISSUED BY:

City of Polokwane
PO Box 11
POLOKWANE
0700

TEL : (015) 290 2148

PREPARED BY:

BVi Consulting Engineers
PO Box 2967
PRETORIA
0001

TEL : (015) 291 5400

NAME OF TENDERER :

CITY OF POLOKWANE

PM56/2020: COMPLETION OF CURRENT CONSTRUCTION PHASE OF AN RDP COMBO SPORTS COMPLEX AT MOLEPO (MULTI-YEAR)

ADDENDUM NO 1

This Addendum forms part of the Tender Documents.

Each Tenderer for this Contract shall incorporate the following amendments and additions in his Tender.

Each Tenderer is required to acknowledge receipt and acceptance of the amendments and additions contained in this Addendum and to submit the completed addendum with his Tender.

No pages may be removed from the Addendum.

C2.2 BILL OF QUANTITIES

REPLACE THE TOTAL BILL OF QUANTITIES IN THE TENDER DOCUMENT WITH THE BILL OF QUANTITIES ON THE FOLLOWING PAGES:

2. ACCEPTANCE AND INCORPORATION OF ADDENDUM

I/We accept that Addendum No 1 forms part of the Tender Documents.

I/We confirm that I/we -

- (a) have noted the contents of this Addendum
- (b) have fully considered this Addendum
- (c) have incorporated the amendments and additions contained in this Addendum in my/our Tender for Contract No. PM56/2020.

SIGNED ON BEHALF OF THE TENDERER :

NAME OF SIGNATORY (BLOCK LETTERS) :

NAME OF TENDERER (BLOCK LETTERS) :

TENDERER'S ADDRESS :
.....

TENDERER'S TEL NO :

TENDERER'S FAX NO :

SIGNATURES OF WITNESSES : 1.
2.

NAMES OF WITNESSES (BLOCK LETTERS) : 1.
2.

DATE :

COMPLETION OF CURRENT CONSTRUCTION PHASE OF AN RDP COMBO SPORTS COMPLEX AT GA-MOLEPO

SCHEDULE A

SECTION 1: PRELIMINARY & GENERAL

ITEM NO	PAYMENT	DESCRIPTION	UNIT	QTY	RATE	AMOUNT (R)
1	SABS 1200 A	SECTION 1: PRELIMINARY & GENERAL				
1.1	8.3	FIXED-CHARGES AND VALUE RELATED ITEMS	Sum	-	-	
1.2	8.4	TIME-RELATED ITEMS	Sum	-	-	
1.3	PSA-6	PROVISIONAL AMOUNTS BY ENGINEER				
1.3.1	PSA-6.1	Independent testing specified by the Engineer	Prov. Sum	-	-	35,000.00
1.3.2		Overheads, Charges and Profit on Item 1.3.1 above	%	35,000.00		
1.3.3	PSA-6.6	Repair of combi-courts final surface.	Prov. Sum	-	-	100,000.00
1.3.4		Overheads, Charges and Profit on Item 1.3.3 above	%	100,000.00		
1.3.5	PSA-6.9	Provision for PSC meetings (maximum 10 persons) R140 per person/meeting.	Prov. Sum	-	-	14,000.00
1.3.6		Overheads, Charges and Profit on Item 1.3.5 above	%	14,000.00		
1.3.7	PSA-6.10	Provision for community liaison officer @ R4,500./month	Prov. Sum	-	-	18,000.00
1.3.8		Overheads, Charges and Profit on Item 1.3.7 above	%	18,000.00		
1.3.11	PSA-6.15	Provision for athletics track	Prov. Sum	-	-	6,500,000.00
1.3.12		Overheads, Charges and Profit on Item 1.3.11 above	%	6,500,000.00		
1.4		HEALTH & SAFETY				
		Compliance with the Occupational Health and Safety Act (Act 85 of 1993) and applicable latest regulations (Construction Regulations, 2015), and the Employers Health & Safety Specification bound into this document:				
1.4.1		Preparation of a Health and Safety Plan	Sum	-	-	
1.4.2		Provision of a Health and Safety file	Sum	-	-	
1.4.3		Provision of construction supervisors	Sum	-	-	
1.4.4		Provision of a safety officer (full-time and registered with the SACPCMP as a Construction Health & Safety Practitioner)	Sum	-	-	
1.4.5		Health and Safety training	Sum	-	-	
1.4.6		Provision of personal protective clothing and equipment (Including covid19 precaution)	Sum	-	-	
1.4.7		Provision of safety fences, signs and barricades	Sum	-	-	
Total Carried Forward To Summary						

COMPLETION OF CURRENT CONSTRUCTION PHASE OF AN RDP COMBO SPORTS COMPLEX AT GA-MOLEPO

SCHEDULE A

SECTION 2: BULK EARTHWORKS

ITEM NO	PAYMENT	DESCRIPTION	UNIT	QTY	RATE	AMOUNT R
2		SECTION 2: BULK EARTHWORKS				
2.1	SABS 1200 D	EARTHWORKS				
2.1.1	PSD 8.3.2	Restricted Excavation				
		Excavate eroded openings in all materials, and use for backfill on embankments				
	PSD 8.3.2.1	Depth up to 1,0 m	m ³	451.4		
	PSD 8.3.2.2	Depth over 1,0 m and up to 2,0 m	m ³	40.0		
	PSD 8.3.2.3	Depth over 2,0 m and up to 3,0 m	m ³	23.0		
2.2	8.3.4	Importing of materials:				
	8.3.4.1	Extra over item 2.1.1 for importation of materials from commercial sources	m ³	-		Rate Only
	8.3.4.2	Extra over item 2.1.1 for importation of materials from borrow pits	m ³	-		Rate Only
	8.3.4.3	Opening and closing down of designated borrow pit	Sum	-		Rate Only
2.3	8.3.10	Topsoiling	m ²	-		Rate Only
2.4	8.3.11	Grassing cover by Hydroseeding	m ²	-		Rate Only
Total Carried Forward To Summary						

COMPLETION OF CURRENT CONSTRUCTION PHASE OF AN RDP COMBO SPORTS COMPLEX AT GA-MOLEPO

SCHEDULE A

SECTION 3: BUILDING WORKS

ITEM NO	PAYMENT	DESCRIPTION	UNIT	QTY	RATE	AMOUNT R
3	1200 PD	SECTION 3: BUILDING WORKS				
		CLUB HOUSE, PUBLIC ABLUTIONS AND CARETAKER QUARTERS				
	PD.02	Plaster work				
	.01	25mm thick, steel-float finish	m ²	10.0		
	PD.04	Doors and Windows				
	PD.04.02	Steel door frames with doors				
	.01	Supply and fit new double pressed steel door frame, door, locks and hinges to 220mm wall. 1981 mm x 1220 mm x 50 mm	No.	1.0		
	.02	Supply and fit new single door complete with lock, hinges and paint door frame. 1981 mm x 610 mm x 50 mm	No.	4.0		
	.03	Treat wooden doors with wood preservative 1981 mm x 610 mm x 50 mm	No.	9.0		
	PD.07	Joinery				
	.02.01	Skirtings 67 mm x 12 mm	m	30.0		
	PD.08	Miscellaneous work				
	.01	Paintwork on plastered wall	m ²	26.0		
	.02	Tiling	m ²	5.0		
	.03	Soap dispenser	No.	1.0		
	.04	Refitting of doors	No.	6.0		
	.05	Fitting of cupboards	No.	2.0		
	.06	Granite top silicon sealant	m	30.0		
	.07	Refitment of roller shutter door	No.	1.0		
	.08	Supply and fit stoves	No.	2.0		
	.09	New gas installation complete with 2 x 25 kg gas bottles in protective cage, shut-off valve and piping	No.	1.0		
	.10	Service fire extinguisher	No.	6.0		
	.11	Replace door lock and handle	No.	2.0		
	.12	Treat area around club house with weed killer	m ²	100.0		
	.13	Clean sewer pipe system	m	30.0		
Total Carried Forward To Summary						

COMPLETION OF CURRENT CONSTRUCTION PHASE OF AN RDP COMBO SPORTS COMPLEX AT GA-MOLEPO

SCHEDULE A

SECTION 4: ELECTRICAL

ITEM NO	PAYMENT	DESCRIPTION	UNIT	QTY	RATE	AMOUNT R
4		SECTION 4: ELECTRICAL				
4.1		BOREHOLE				
4.1.2		Replace conduit and supply cable	m	40.0		
4.1.3		Replace pump control panel	No.	1.0		
4.2		BUILDINGS				
4.2.1		Remount sockets	No.	6.0		
4.2.2		Install light switches	No.	3.0		
4.2.3		Replace bulkhead diffusers	No.	20.0		
4.2.4		Replace channel fluorescent luminaire	No.	3.0		
4.2.5		Install stove coupler	No.	1.0		
4.3		DISTRIBUTION BOARD				
4.3.1		Install distribution board legend cards	No.	4.0		
4.3.2		Replace distribution board door latch	No.	1.0		
4.3.3		Install 10A SP circuit breaker	No.	1.0		
4.3.4		Surge Protector	No.	1.0		
4.4		ELECTRICAL DISTRIBUTION KIOSK				
4.4.1		Door and face plate	No.	1.0		
4.4.2		Surge arrestors	No.	6.0		
4.5		LIGHT POLE				
4.5.1		Mounted luminaire	No.	4.0		
Total Carried Forward To Summary						

COMPLETION OF CURRENT CONSTRUCTION PHASE OF AN RDP COMBO SPORTS COMPLEX AT GA-MOLEPO

SCHEDULE A

SECTION 5: STORMWATER DRAINAGE

ITEM NO	PAYMENT	DESCRIPTION	UNIT	QTY	RATE	AMOUNT R
5		SECTION 5: STORMWATER DRAINAGE				
5.1		BULK STORMWATER DRAINAGE				
	SABS 1200 C	SITE CLEARANCE				
	8.2.1	Clear and grub	m	1,150.0		
	8.2.2	Remove and grub large trees and tree stumps of girth				
		a) Over 1m and up to and including 2m	No.	5.0		
	SABS 1200 DA	EARTHWORKS (SMALL WORKS)				
	8.3.1	Excavation				
	8.3.1 (b)	Excavate in all materials and use for embankment or backfill or dispose, as ordered	m ³	250.0		
		Rip, scarify, wet and compact the exposed ground surface to a depth of 150mm	m ²	1,691.0		
	SABS 1200 DK	GABIONS AND PITCHING				
	8.2.1	Surface preparation for bedding of gabions	m ²	80.0		
	8.2.2	Gabions	m ³	24.0		
	SABS 1200 GA	CONCRETE SMALL WORKS				
	8.2	Scheduled formwork items				
	8.2.1	Rough				
	(a)	Trapezoidal channel profile (1.2m x 0.1m x 226 no.)	m ²	41.0		
	8.3	Scheduled reinforcement items				
	8.3.2	High tensile welded mesh (Ref 395)	m ²	925.0		
	8.4	Scheduled concrete items				
	8.4.1	Prescribed mix concrete				
	(a)	Channels (30MPa/19mm ready mix)	m ³	98.0		
	8.5	Joints				
	(a)	Saw cut	m	195.0		
	(b)	Expansion joints (soft board)	m	85.0		
	SABS 1200 LE	STORMWATER DRAINAGE (PIPES)				
	8.2.1	Supply, Lay, Set out, Joint, Bed (Class B), and Test pipeline of a spigot and and socket 450mm Class 75D	m	15.0		

Total Carried Forward To Summary

SUMMARY OF SECTIONS

SECTION	DESCRIPTION	AMOUNT (R)
1	SECTION 1: PRELIMINARY & GENERAL	
2	SECTION 2: BULK EARTHWORKS	
3	SECTION 3: BUILDING WORKS	
4	SECTION 4: ELECTRICAL	
5	SECTION 5: STORMWATER DRAINAGE	
	SUBTOTAL	
	Add 10% CONTINGENCIES	
	SUBTOTAL	
	Add 15% VAT	
	Total Carried Forward To Summary Of Schedules	